

TRANSMOBIL TM Installation Carrier – Transporting and laying curb stones

A compact universal machine – transport and handling of palletized building material and vacuum installation all in one.

The powerful vacuum laying unit allows the immediate installation of heavy construction elements – effortless and without physical strain.

Crawler with rubber tracks for uneven terrain, combined with a vacuum hose lifter HE-150 and operating valve unit BE-Sprint-2 incl. standard suction plate with 150 kg carrying capacity.

- Hydraulic mast angling in seconds
- Boom can be swung easily and the installation material positioned exactly

Туре	Power	Reach in (mm)	Working Load Limit WLL of Vacuum Laying Unit* lbs (kg)	Payload lbs (kg)	Dead Weight lbs (kg)	Order- Number
TM-150-D-A-	diesel engine 9,6 kW	118	330	3,300	approx. 3,400	52220012
XL	Hatz Silent Pack	(3,000)	(150)	(1,500)	(1,540)	
TM-150-D-A-	diesel engine 9,6 kW	118	330	3,300	approx. 3,400	52220014
SILENT-XL	Hatz Silent Pack	(3,000)	(150)	(1,500)	(1,550)	
TM-GGP	Essential add-on once the lifting capacity exceeds 150 kg. Installation material, such as kerb stones serve as counterweight.			552 (250)	22 (10)	42220070

Highest Safety Standards:

The SAFESTOP ensures that the knuckle boom jib cannot swing into the traffic area


TM-150-D-A-XL:

with sound insulated Hatz Silent Pack diesel engine

• TM-150-D-A-SILENT-XL:

with sound insulated Hatz Silent Pack diesel engine with additional sound proofing measures.

Noise emission < 80 dB



More than 1.000 different suction plates and accessories are available, see page 55 for examples

^{*} With more poweful lifting hose unit, proper suction plate etc. and platform for counterweight TM-GGP upgradeable to 200 kg lifting capacity when fully extended and up to 250 kg at reduced outreach of 500 mm.